

KANSAS

Form CP-3
Rev. 6-26-62



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1967

CONSERVATION DIVISION
Wichita, Kansas

10-19-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued October 9, 1967.

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas 67530

Lease Name Lincoln Well No. #-1

Location NW SE SE Sec. 29 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3849'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:00 AM Day 18th Month October Year 1967

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cemented with 175 sacks. 3848' of 5 1/2" long string, cemented with 100 sacks. Plug back T.D. 3670'. Top perforation 3543'. Casing was plugged at 3100', 5 sacks of cement was dumped, through the dump bailer on bridge at 3100', with cement from 3100' to 3060'. 75' of 5 1/2" long string was recovered from the hole. Hole was flowing with water, and was squeezed. 10 sacks of Gel-Mud and 80 sacks of cement was pumped in the surface pipe, through an 8 5/8" swage, to a pressure of 200 lbs, with cement from 240' to the base of the cellar. This cementing was done by Glenn & Smith Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/19/67
INV. NO. 6520-W