

15.145.19063.0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1975

CONSERVATION DIVISION  
Wichita, Kansas

1-20-1975

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company

Complete Address 300 Writers Center IV Bldg., Denver, Colorado 80222

Lease Name Cossman Well No. 1

Location SW NE SW Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3856'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Charlie Crowe Casing Pulling

Address Box 706, Hays, Kansas 67601 License No. 733

Operation Completed: Hour 11 A Day 1 Month 15 Year 1975

The above well was plugged as follows:

Total Depth 3856' 8 5/8 csg set at 933' cwc 500 sk.

5 1/2 csg set at 3853' cw 125 sk cem.

Filled 5 1/2 csg W/sd (3856-3800) dumped 4 sk cmt W/dump bailer. (3800-3770)

Cutoff & recovered 2826' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water -released plug & pumped 120 sk

60-40 poz cement by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing  
Well Plugging Supervisor

DATE 1/22/75

INV NO. 690-W