

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145-00783.0000 (of this well)

RECEIVED
STATE CORPORATION COMMISSION

DEC 06 1976

CONSERVATION DIVISION
Wichita, Kansas

12-6-1976

Operator's Full Name A. L. Abercrombie, Inc.
Complete Address 801 Union Center, Wichita, Kansas 67202
Lease Name Schrope Well No. 1
Location C E/2 E/2 SE SW Sec. 27 Twp. 21 Rge. (E) (W) 16
County Pawnee Total Depth 3868'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 ^{PM} Day 2 Month 12 ¹² Year 1976

The above well was plugged as follows:

Total Depth 3868' 8 5/8 csg set 992' cwc 425 sx.

5 1/2 csg set 3855' cw 150 sx.

Filled 5 1/2 csg with sand (3868'-3820') dumped 4 sk cem W/dump bailer. (3820'-3790')

Cutoff & recovered 2524' of 5 1/2 csg.

Plg'd 8 5/8 csg with drilling mud to 360' -set rock & sand bridge (360'-350')

Filled with readymix cem. from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Massey
Well Plugging Supervisor

DATE 12-6-76

INV. NO. 4276-W