

KANSAS



CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center Wichita, Kansas 67202

Lease Name Morris Well No. 3

Location CNL SW SW Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3861 1/8

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour Day 21 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3861 1/2' 8 5/8 csg set at 986' CWC

5 1/2 csg set at 3848' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3825-3861 1/2) Dumped 5 sk cmt W/dump bailer. (3795-3825)

Cutoff and recovered 2635' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 375' -set rock & sand bridge (350-375)

Dumped 5 yds readymix cmt (350 to base of cellar)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 3-23-72
INV. NO. 5379-12