



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1975
CONSERVATION DIVISION
Wichita, Kansas

1-20-1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company

Complete Address 300 Writers Center LW Bldg., Denver, Colorado 80222

Lease Name Cossman Well No. 2

Location S/2 NW SW Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3875'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Charlie Crowe Casing Pulling

Address Box 706, Hays, Kansas 67601 License No. 733

Operation Completed: Hour 12:30 P Day 1 Month 15 Year 1975

The above well was plugged as follows:

Total Depth 3875' 10 3/4 csg set at 990' cwc 500 sk.

5 1/2 csg set at 3863' cw 125 sk cem.

Filled 5 1/2 csg W/sd (3875-3850) dumped 4 sk cmt W/dump bailer. (3850-3820)

Cutoff & recovered 2140' of 5 1/2 csg.

Pumped down 20 3/4 csg with 35 sk gel & water -released plug & pumped 140 sk

60-40 poz cem. by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo L. Marston
Well Plugging Supervisor

DATE 1/22/75

NV. NO. 691-W