

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1963  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mc Adams Pipe & Supply Co

Complete Address: 2700 Main Great Bend, Kans

Lease Name W. K. Bell Well No. 7

Location NE NE NE Sec. 27 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3879

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc

Address: Ellinwood, Kans License No. 462

Operation Completed: Hour 2PM Day 10 Month 7 Year 63

The Above well was plugged as follows:

10" 972' circulated with cement - 7" 3857' with 100 sax cement.  
PB to 3857' - perforated 3840' - filled with sand to 3830', set 5  
sax cement with dump bailer-

Pulled 2513' 7" - filled hole with heavy rotary mud to 400', set 25 sax  
cement at 400', heavy rotary mud to 180', set 25 sax cement at 180',  
heavy rotary mud to 30', set 10 sax cement to bottom cellar.

Mudding by Maclaskey vacuum pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7-15-63  
INV. NO. 7404-W

Signed: [Signature]  
Well Plugging Supervisor