

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Mc Adams Pipe & Supply

Complete Address: 2700 Main Great Bend, Kans

Lease Name W. K. Bell Well No. 8

Location NE NW NE Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3873

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc

Address: Ellinwood, Kans License No. 462

Operation Completed: Hour 9:30AM Day 10  Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 977' circulated with cement - 5 1/2" c 3870' with 100 sax cement.  
Sand back to 3850', set 5 sax cement with dump bailer - pulled 2700'  
5 1/2" - filled hole with heavy rotary mud to 390', set 20 sax cement  
at 390', heavy mud to 180', set 20 sax cement at 180', heavy mud to  
35', cement 35' to bottom cellar.

Mudding by Maclaskey vacuum pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7-15-63  
INV. NO. 7406-W

Signed: Eaton Lester  
Well Plugging Supervisor