

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Smith Well No. 1

Location SE NE NW Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3876

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 3:30PM Day 10 Month 2 Year 64

The Above well was plugged as follows:

8 5/8" 598' circulated with cement - 5 1/2" 3875' with 75 sax cement -

Sanded back to 3490', set 4 sax cement with dump bailer - pulled 2680' 5 1/2"-
pumped hole full heavy gel mud at 1000# pump pressure - pumped wiper plug
and squeezed with 100 sax cement at 1100# pump pressure - cement to bottom
cellar.

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Kelly
Well Plugging Supervisor

DATE 2/14/64

INV. NO. 8636-111