

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -145-00779-0000 (of this well)

Operator's Full Name RUSS CASING PULLING INC.

Complete Address BOX 1082 GREAT BEND, KANS. 67530

Lease Name HERR Well No. #1

Location SE-C-SW-NW Sec 27 Twp. 21 Rge. 16 (E) (W) W

County PAWNEE Total Depth 3896 FE

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE KANS. 67524 License No. 683

Operation Completed: Hour 2:15 PM. Day 10<sup>th</sup> Month JAN Year 1980

The above well was plugged as follows:

8 3/8" 992 FE SP. CUC 1/2" - 5 1/2" SET AT 3869 FE w/ 150 ST.  
2838 FE TOP OF CEMENT ON LONG STRING. - BOTTOM SAND TO  
3850 FE AND 5 ST CMT. - PIPE PARTED SEVERAL TIMES RECOVERED 1600 FE  
ORDERED - 130 ST 50/ POZMAN 4% GEL. -> 25 ST GEL. -> 5 ST HULL'S 78 3/8 PLUG.  
(PUMPED IN WITH PUMP TRUCK.)  
PUT IN - 3 ST HULL'S -> 25 ST GEL - 2 ST HULL'S - RELEASE PLUG.  
AND 130 ST CMT. -> MAX. PRESSURE 400 LBS SHUT IN 150 LBS  
CEMENTED BY SUN CEMENTING

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

Signed: Marion Schmidt  
Well Plugging Supervisor

INVOICED

JAN 14 1980

DATE 1306 CONSERVATION DIVISION  
Wichita, Kansas

NO. 1-17-80