

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pipe Pullers, Inc.

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name W. N. K. Bell Well No. 4

Location C NE SE NW  
990' NSL & 2310' EWL NW/4 Sec. 27 Twp. 21 Rge. (E) (W) 16.

County Pawnee Total Depth 3870'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Toels

Address        License No. 462

Operation Completed: Hour 2:15 P Day 17 Month 5 Year 1972

The above well was plugged as follows:

- Total Depth 3870' 13" at 120' cwc: 8 5/8 csg 992 cwc: 437 sk.
- 5 1/2 csg set at 3869' cw 100 sk cmt
- Filled 5 1/2 csg W/sd (3850-3870) Dumped 5 sk cmt W/dump bailer. (3815-3850)
- Cutoff and recovered 2017' of 5 1/2 csg.
- Filled ~~5 1/2~~ csg W/mud to 375' -set rock & sand bridge (350-375)
- Dumped 5 yds readymix cmt (base of cellar to 350')

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansury  
Well Plugging Supervisor

DATE 5/25/72  
INV. NO. 5740-W