

15.145.61467.0000

Form CP-3
Rev. 6-4-68

KANSAS

28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pipe Pullers, Inc.

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name W. K. Bell Well No. 3

Location C NE SW NE Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. _____

Operation Completed: Hour 5 P Day 8 Month 5 Year 1972

The above well was plugged as follows:

Total Depth 3865' 13 3/8 csg at 97' cwc 8 5/8 csg set at 987' cwc

5 1/2 csg set at 3865' cw 100 sk cmt.

5 1/2 csg PB 2047' and perf. (30218').

Set 5 1/2 wood plug at 2980' -poured 50' sd -dumped 5 sk cmt W/dump bailer. (2875-2980)

Cutoff and recovered 2300' of 5 1/2 csg.

Mud to 375' -set rock & sand bridge (350-375')

Dumped 5 yds readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red Z. Mussey
Well Plugging Supervisor

INVOICED

DATE 5-15-72

INV. NO. 5709-W