

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pipe Pullers, Inc.
Complete Address Box 486 Ellinwood, Kansas 67526
Lease Name W. K. Bell Well No. 2
Location SW SW NE Sec. 27 Twp. 21 Rge. (E) (W) 16
County Pawnee Total Depth 3864'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.

Operation Completed: Hour 4 P Day 28 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 3864' 9 5/8 csg set at 985' cwc 500 sk.
7" csg set at 3864' cw 100 sk cmt.
Filled 7" csg W/sd (3820-3864) Dumped 6 sk cmt W/dump bailer. (3785-3820)
Cutoff and recovered 2010' of 7" csg.
Filled 9 5/8 csg with mud to 375' -set rock & sand bridge (350-375)
Filled with readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 7-5-72
INV. NO. 5984-60