

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pipe Pullers, Inc.

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name W. K. Bell Well No. 10

Location N/2 SE NE Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3869'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4 P Day 30 Month 5 Year 1972

The above well was plugged as follows:

Total Depth 3869' 10 3/4 csg set at 983' cwc 700 sk.

7" csg set at 3836' cw 100 sk cmt.

Filled 7" csg W/sd (3825-3869) dumped 6 sk cmt W/dump bailer. (3790-3825)

Cutoff and recovered 2031' of 7" csg.

Mud to 375' -set rock & sand bridge (350-375)

Dumped 6 yds readymix cmt (30-350) Mud to 10" capped with 3 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Slattery
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5812-62