

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pipe Pullers, Inc.

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name W. K. Bell Well No. 9

Location SW SE NE Sec. 27 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3877'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 11 A Day 7 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3877' 8 5/8 csg set at 985' cwc 430 sk.

5 1/2 csg set at 3872' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3840-3877) Dumped 5 sk cmt W/dump bailer. (3805-3840)

Cutoff and recovered 2039' of 5 1/2 csg.

Filled 8 5/8 csg W/mud to 375'- set rock & sand bridge (350-375)

Dumped 5 yds readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 8-10-72

INV. NO. 6141-10