

RECEIVED
15.145.00765.0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First, Wichita, Kansas 67202

Lease Name Bowman Well No. 4

Location C: W/2 NE NE Sec. 11 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3790'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Nicholas Pipe Pulling

Address Box 373 Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 1:30 P Day 17 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3790' 8 5/8 csg set at 980' cwc 475 sk.

5 1/2 csg set at 3788' cw 100 sk cmt.

Filled 5 1/2 csg with sand (3790-3770) dumped 4 sk cmt with dump bailer. (3740-3770)

Cutoff and recovered 2406' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 400' -set rock & sand bridge (400-380)

Filled with readymix cement from 380' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 6/21/74

INV. NO. 9335-W