

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First, Wichita, Kansas 67202

Lease Name Bowman Well No. 2

Location NE NE NE Sec. 11 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3791'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 3:30 P Day 12 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3791' 8 5/8 csg set at 971' cwc 475 sk.

5 1/2 csg set at 3783' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3791-3765) dumped 4 sk cmt W/dump bailer. (3735-3765)

Cutoff and recovered 3059' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 400' -set rock & sand bridge (400-380)

Filled with 5 1/2 yds readymix cement from 380' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mason
Well Plugging Supervisor

INVOICED

DATE 6/18/74

INV. NO. 9309-W