

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 04 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas 4-4-1977

API Number 15 - 145 - 00763.0000 (of this well)

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First, Wichita, Kansas 67202

Lease Name Bowman Well No. 1

Location SE NW NE Sec. 11 Twp. 21 Rge. (E) (W) 16

County Rawnee Total Depth 3783'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholos Casing Pulling

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 3 P Day 31 Month 3 Year 1977

The above well was plugged as follows:

Total Depth 3783' 8 5/8 csg set 985' cwc 500 sx.

5 1/2 csg set 3776' cw 100 sx cem.

Filled 5 1/2 csg W/sd (3783'-3750') dumped 4 sx cem W/dump bailer. (3750'-3720')

Cutoff & recovered 2755' of 5 1/2 csg.

Drlg. mud from TD to 290' -set rock & sand bridge (290'-280')

Filled with RMC from 280' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-5-77

INV. NO. 4903-W