



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

CONSERVATION DIVISION
Wichita, Kansas

12-2-1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. L. A. Chubb of Duke Drilling Co. has this date requested permission to plug the following described well:

Mr. Chubb guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City 5, Mo.

Lease Name: Smith Estate Well No. # 19

Location: SE SE NE Sec. 16 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3500 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Chubb was instructed to plug the well as follows:

285' of 8 5/8" surface pipe, cemented with 220 sacks.
Fill hole with drilling mud to 275', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent