

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 3 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughan Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Richardson Well No. # 1

Location: NE NW SE Sec. 20 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3539' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

246' of 8 5/8" surface pipe, cement circulated with 210 sacks.  
Fill hole with drilling mud to 225', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*