



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 26 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Pully of Forbes Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Company

Complete Address: 925 Patten Road, Great Bend, KANSAS

Lease Name: Korth Well No. #1

Location: SW-SW-NW Sec. 20 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3495 Oil Well x

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Pully was instructed to plug the well as follows:

213 feet of 8 5/8 inch surface pipe circulated with 250 sacks cement.  
3456 1/2 feet of 5 1/2 inch long string cemented with 50 sacks sand to 3435  
cemented with 3 sacks cement. Mud to 180 feet; 10 feet rock bridge cemented with  
25 sacks, mud to 40 feet; 10 feet rock bridge, 10 sacks cement to base of  
cellar.

Very truly yours,

\_\_\_\_\_  
 Conservation Division Agent