



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Sage Drlg. Co. Inc. has this  
date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corp.

Complete Address: 1000 Century Plaza Wichita, Ks

Lease Name: Russell Well No. 1

Location: NE/SE/NW Sec. 25 Twp. 21s Rge. 14 (E)(W) W

County: Stafford Total Depth 3767 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Freeman was instructed to plug the well as follows:  
365 ft of 8 5/8 surface pipe cemented with 250 sacks. Set  
bottom plug at 550 ft, 65 sacks cement. 2nd plug at 300  
ft, 25 sacks cement. Mud to 40 ft, plug, 1/2 sacks hulls,  
10 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by

Very truly yours,

*L. Russell Biberstein*  
Conservation Division Agent