

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 33 Twp. 21 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Petroleum, Inc.

Lease Name KRAMPE 'B' Well No. 1

Office Address 311 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 2, 19 55

Application for plugging filed January 2, 19 55

Application for plugging approved January 2, 19 55

Plugging commenced January 2, 19 55

Plugging completed January 2, 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 270' and set first

wooden plug at 270'. Placed 1/3

sack hulls on top of plug. Displaced

20 sacks cement through drill pipe on

top of hulls. Mudded up to 35' and set

second wooden plug at 35'. Placed 1/3

sacks hulls on top of plug and filled

hole to base of well cellar with 10

sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1955

Name of Plugging Contractor Garvey Drilling Company

Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Karl E. Becker (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker

311 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 55

My commission expires 8-11-58 Notary Public.

PLUGGING
REC SEC 33 T. 21 R. 14 W
BOOK PAGE 88 LINE 37

WELL LOG

15.185.00687.0000

COMPANY **Petroleum, Inc.**

SEC. **33** T. **21** R. **14W**

FARM **KRAMPE 'B'**

NO. **1**

LOC. **SE SE NW**


TOTAL DEPTH **3850'**

COUNTY **Stafford County, Kansas**

COMM. **December 22, 1954.**

COMP. **January 2, 1955.**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 278' w/250 sax.**

ELEVATION **1945 RB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

268	Sand
278	Shale
320	Shale & Shells
400	Sand
858	Red Bed & Sand
885	Anhydrite
1635	Shale & Shells
3422	Line & Shale
3703	Line
3717	Line & Shale
3757	Cherty Line
3818	Line & Shale
3850	Line
3850	T.D.

Tops:

Hebner:	3301 (-1356)
Toronto:	3323 (-1378)
Douglas:	3344 (-1399)
Brown Lime:	3422 (-1477)
Lansing:	3431 (-1486)
Simpson:	3753 (-1808)
Arbuckle:	3809 (-1864)

State of KANSAS
County of SEDCWICK

SS:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the KRAMPE 'B' #1 well.

Karl E. Becker

Subscribed and sworn to before me this 19th day of January, 1955

My Commission Expires: 8-11-58

PLUGGING
 FILE SEC 33 21 R 14 W
 BOX PAGE 88 LINE 37
 NOTARY PUBLIC

RECEIVED
 STATE COMMISSION
 JAN 27 1955
 CONSERVATION DIVISION
 Wichita, Kansas