


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 33 Twp. 21 Rge. 14 (NW) (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NW  
Lease Owner Petroleum, Inc.  
Lease Name Cox 'B'  
Office Address 100 Derby Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 29, 19 51  
Application for plugging filed December 29, 19 51  
Application for plugging approved December 29, 19 51  
Plugging commenced December 29, 19 51  
Plugging completed December 29, 19 51  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3820 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 256'. Placed wooden plug at  
256'. Cemented and displaced 15 sax cement  
through drill pipe on top of plug. Mudded  
up to, and placed second wooden plug at 35'.  
Placed 10 sax cement on top of plug filling  
hole to bottom of cellar.

JAN - 4 1952 1-4-1952

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eric H. Jager (employee of owner) or ~~owner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager  
100 Derby Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January, 19 52

Charlotte Heidman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
FILE SEC 33 T 21 NW 1/4  
PAGE PAGE 135 LIST 5

DRILLER'S LOG COX 'B' #1

Petroleum, Inc., Lease Owner

Section 33, Twp. 21S, Rge. 14W

Garvey Drilling Co., Contractor

Location: NW NW NW

Drilling Commenced: December 17, 1951

County: Stafford

Drilling Completed: December 29, 1951

Production: D & A

Casing Record: 8 5/8" @ 256' w/175 sax

R.T.D.: 3820'

All figures below indicate bottom of formation:

- 50 Surface Clay
- 230 Sand
- 310 Shale & Shells
- 400 Sand
- 866 Red Bed
- 894 Anhydrite
- 1690 Shale & Shells
- 2400 Lime & Shale
- 2670 Shale & Shells
- 3235 Lime & Shale
- 3355 Lime
- 3419 Shale
- 3438 Lime
- 3465 Lime & Shale
- 3670 Lime
- 3724 Lime & Shale
- 3754 Viola Chert
- 3804 Shale
- 3820 Lime

Tops:

- Heebner: 3301 (-1355)
- Brown Lime: 3419 (-1473)
- Lansing: 3428 (-1482)
- Arbuckle: 3805 (-1859)

3820' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By

*Eric M. Jager*  
Eric M. Jager

STATE OF KANSAS )

COUNTY OF SEDGWICK )

JAN 22 1952  
**PLUGGING**  
 FILE SEC 35 T 27 R 14S  
 BOOK PAGE 135 LINE 5

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 4th day of January, 1952.

*Charlotte Friedman*  
Notary Public

My commission expires: October 13, 1954