

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15185.00696.0000

LEASE NAME Strobel

WELL NUMBER 2

SPOT LOCATION SW NW SW

SEC. 33 TWP. 21S RGE. 14 ~~NESE~~(W)

COUNTY Stafford

Date Well Completed 12-17-56

Plugging Commenced 2-23-84

Plugging Completed 2-24-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHAPMAN EXPLORATION, INC.

ADDRESS 404 Cities Service Bldg., Tulsa, Oklahoma
74119

PHONE (918) 582-2247 OPERATORS LICENSE NO. 6939

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? Sent with application.

Producing formation LKC Depth to top 3566 bottom 72 T.O. 3905

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3566	72	8-5/8	285	None
Arbuckle	water	3854	3905	5-1/2	3903	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set. Pumped into 5-1/2" at rate of 6 barrels per minute at zero pressure. Mixed 1 sack hulls, 50 sacks 50/50 poz 3% cc 2% gel and 100 sacks 50/50 poz 3% cc 2% gel and pump into 5-1/2" at final shut in pressure of 100 psi. Mixed 150 sacks 50/50 poz and pump down 8-5/8" and shut in at 100 psi. Cut 5-1/2" and 8-5/8" off at 3' below GL. Top with hand mixed cement and weld on plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementers License No. _____
Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Virgil L. Johnson (employee of operator) ~~XX~~

~~Representative~~ of above-described well), being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
3-12-1984
MAR 12 1984

(Signature) Virgil L. Johnson
(Address) 404 Cities Service Bldg.
Tulsa, Oklahoma 74119

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1984
Wichita, Kansas

Marjorie J. Kiger
Notary Public

My Commission expires: June 7, 1984