


STATE OF KANSAS  
STATE-CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

McPherson County, Sec. 12 Twp. 21 Rge. 1 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE NE NW  
Lease Owner Donald C. Slawson  
Lease Name Doersken #2 Well No.  
Office Address (Goessel-Hunton W.F. Unit Well No.19)  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2/28/77 19  
Plugging completed 3/2/77 19  
Reason for abandonment of well or producing formation  
depleted.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott  
Producing formation Depth to top Bottom Total Depth of Well 3406  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	216	none
				5 1/2"	3404 1/2	1623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Pushed wood plug to 3000', sanded to 2980' and ran 5 sacks cement.  
Loaded hole with salt water, shot pipe at 2007', 1812', 1621',  
pulled 41 joints. Bailed fluid down to 240', set rock bridge and  
cemented hole with 4 1/2 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 07 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING CHASE, KANSAS  
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

(Address) March, 19 77

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 77

Margaret Melcher  
Notary Public.

My commission expires



15-113.02131.0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- CHAMPLIN OIL & REFINING CO.  
Farm- Duerksen No. 2

SEC. 12 T. 21 R. 1W  
SE NE NW

Total Depth. 3406'  
Comm. 6-30-58 Comp. 7-10-58  
Shot or Treated.  
Contractor. Sierra Petroleum Co.  
Issued. 3-28-59

County McPherson  
KANSAS



Elevation. 1538' KB

Production. 42 BOFD

CASING:

8 5/8" 216 cem w/165 sx.  
5 1/2" 3404.43' cem w/75 sx.

Figures indicate Bottom of Formations.

surface clay	30
sand & shale	75
shale	90
shale & shells	295
Anhydrite	315
shale & lime	350
Anhydrite	375
lime & shale	870
lime, shale & sand	965
shale & lime	2570
lime	2800
lime & shale	2990
Miss. lime & chert	3035
chert & shale	3085
lime & chert	3210
lime	3253
shale & lime	3305
shale	3406
Total Depth	

TOPS:

Anhydrite	295
Brown Lime	2340
Lansing-Kansas City	2348
Mississippi	2961
Kinderhook (scout)	3270
Hunton	3433.43

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1977

CONSERVATION DIVISION  
Wichita, Kansas