


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

McPherson County. Sec. 12 Twp. 21S Rge. 1 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines. NW SW SE  
Lease Owner Anderson-Prichard Oil Corporation  
Lease Name Wedel Well No. 1  
Office Address Liberty Bank Building, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 3, 19 57  
Application for plugging filed June 3, 19 57  
Application for plugging approved June 3, 19 57  
Plugging commenced June 3, 19 57  
Plugging completed June 3, 19 57  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3433 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	212	8 5/8"	212	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 3433' to 200' - heavy rotary mud and plug  
200' to 154' - 15 sacks cement and 1/2 sack hulls  
154' to 20' - heavy rotary mud and plug  
20' to 6' - 10 sacks cement  
6' to surface - cellar

RECEIVED  
STATE CORPORATION COMMISSION  
6-8-1957  
JUN 8 X 1957

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn W. Peel  
Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Glenn W. Peel (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL

(Signature) BY: Al H. Smith  
P.O. Box 359, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 57

Ruth Brant

Notary Public.

My commission expires April 27, 1960

PLUGGING  
FILE SEC. 12 T. 21 R. 10  
BOOK PAGE 19 LINE 17

DRILLERS' LOG

Company: Anderson-Prichard Oil Corporation

NW SW SE  
Sec. 12, Twp. 21S, Rge. 1W,

Farm Name: Wedel Well No. 1

County: McPherson,  
Kansas

Total Depth: 3433'

Comm: 5/22/57 Comp: 6/3/57  
Contractor: Glenn W. Peel

Elevation:

Production: Dry

Casing: 8 5/8" @ 212' cem.

Figures below indicate bottoms of formations:

Sand and shale	0 -	140
Shale and shells		212
Shale and lime streaks		535
Shale and lime		710
Sand		790
Sand and lime		960
Shale and lime		1300
Shale and lime streaks		1635
Shale and lime		1978
Lime, shells and lime		2135
Shale and lime		2420
Lime		2865
Lime and shale		2980
Chat		3000
Miss. Lime		3015
Lime		3051
Chat		3295
Lime and shale		3433
Total Depth		3433

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 5th day of June, 1957

My commission expires: April 27, 1960

Ruth Brant  
Notary Public

RECEIVED  
STATE OF KANSAS COMMISSIONER

JUN 8 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 12 T. 21 R. 1W  
BOOK PAGE 19 LINE 67