


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

McPherson County, Sec. 12 Twp. 21 Rge. 7 (E) W (W)
SW SW NE



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines _____
Lease Owner O. A. Sutton Oil Properties & Investments
Lease Name Goosen Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11-14-60 _____ 19____
Plugging completed 11-20-60 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3407 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	180'	None
				5-1/2"	3403'	2914'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3407' and found it clear. Sanded from 3407' to 3290' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Set rock bridge from 180' to 170' and ran 20 sacks of cement. Mudded hole to 35', set 5' rock bridge to 30' and ran 8 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1960 11-28-1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 60

My commission expires May 20, 1964 Milton J. Volin Notary Public.



J. S. Sutton & Sons Drilling Co. #1 Coosman
S1 S1 NE Section 12-21S-1W
McPherson County, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1966

CONSERVATION DIVISION
Topeka, Kansas

Commenced - January 16, 1958
Completed - January 27, 1958
Casing - 183' of 8-5/8" with 110 sacks
 3407' of 5 1/2" with 75 sacks
Elevation - 1536 Rotary Bushing

DRILLERS LOG

0 - 180	Surface
180 - 280	Shale
280 - 315	Shale and shells
315 - 635	Shale and shells
635 - 810	Shale
810 - 1085	Shale
1085 - 1360	Shale and shells
1360 - 1530	Shale and lime
1530 - 1825	Shale and lime
1825 - 1997	Shale and lime
1997 - 2150	Shale and lime
2150 - 2320	Lime and shale
2320 - 2362	Lime and shale
2362 - 2419	Lime
2419 - 2519	Lime
2519 - 2608	Lime
2608 - 2661	Lime
2661 - 2781	Lime and shale
2781 - 2861	Shale and lime
2861 - 2938	Shale and lime
2938 - 2967	Lime and shale
2967 - 2995	Lime (cherty)
2995 - 3033	Cherty lime
3033 - 3083	Cherty lime
3083 - 3139	Cherty lime
3139 - 3181	Cherty lime
3181 - 3218	Cherty lime
3218 - 3260	Lime and shale
3260 - 3320	Lime and shale
3320 - 3410	Shale and lime
3410 -	Rotary Total Depth

STATE OF KANSAS }
COUNTY OF SEDGWICK }

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON & SONS DRILLING CO.

By Henry D. Ficken

Subscribed and sworn to before me this 28th day of January, 1958.

Joanna L. Galie
Notary Public

My commission expires May 4, 1959.

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

R

File No. _____ County: McPherson

Location: SW SW NE Sec. 12 Twp. 21 Rge. I (E) (W)

Name of Field: Ritz Canton Total Depth: 3407'

I have this date completed supervision of plugging of:

Lease Name: Goessen Well No. I

Operator's Full Name: O A. Sutton

Complete Address: 407 Insurance Bldg, Wichita Kansas.

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase Kansas. License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:PM Day 20 Month II Year 60

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3407' back to 3390' ran 5sax cement w/ dump
bailer. Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3340' back
to 180' set a 10' rock bridge and 20 sax cement. Filled hole w/ mud from 120' back
to 35' set a 10' rock bridge and 8 sax cement. 8 5/8" surface pipe 3' below ground
level.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1960

CONSERVATION DIVISION
Wichita, Kansas

Signed: Facil M Jones
Conservation Division Agent

Reviewed: Goessen
Field Supervisor

Remarks:

INVOICED

DATE 11-30-60

INV. NO. 2587-15