

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson

County. Sec. 12 Twp. 21S Rge. (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner O. A. Sutton

Lease Name Goossen Well No. 2

Office Address 407 Ins. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed May 1958

Application for plugging filed Nov. 9 1960

Application for plugging approved Nov. 10 1960

Plugging commenced Nov. 11 1960

Plugging completed Nov. 14 1960

Reason for abandonment of well or producing formation Noncommercial

If a producing well is abandoned, date of last production Nov. 9 1960

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation Hunton Depth to top Bottom Total Depth of Well 3398 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	190'	-
				5 1/2	3397'	2890'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from total depth to 3388', 5 sx. cement.
Mud to 190', 10' rock bridge, 20 sx. cement.
Mud to 35', 5' rock bridge, 8 sx. cement

STATE CORPORATION COMMISSION

NOV 17 1960

CONSERVATION DIVISION
Wichita

11-17-1960

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. G. Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. G. Comstock

D. G. Comstock

407 Ins. Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1960

My commission expires Feb. 5, 1964

Sara Wimberly Notary Public.

15.113.19309.0000

J. S. Sutton & Sons Drlg. Co., Goossen #2
NW NW NE Sec. 12-21S-1W
McPherson County, Kansas

Commenced - May 13, 1958
Completed - May 22, 1958
Casing - 190' of 8-5/8" w/150 sacks HA5
5-1/2" at 3397' w/75 sacks common
Elevation - 1537 D. F.

RECEIVED
DEC 15 1966
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

0 - 190	Surface
190 - 445	Shale and lime
445 - 670	Shale and lime
670 - 880	Lime and shale
880 - 1085	Lime and shale
1085 - 1475	Shale and lime
1475 - 1745	Shale and lime
1745 - 1900	Shale and lime
1900 - 2085	Shale and lime
2085 - 2275	Lime and shale
2275 - 2389	Lime and shale
2389 - 2485	Lime
2485 - 2565	Lime
2565 - 2630	Lime
2630 - 2714	Lime
2714 - 2795	Lime
2795 - 2870	Lime and shale
2870 - 2939	Lime
2939 - 2957	Shale
2957 - 3012	Mississippian
3012 - 3047	Mississippian lime
3047 - 3082	Mississippian (cherty)
3082 - 3120	Lime (chert)
3120 - 3163	Lime (cherty)
3163 - 3196	Mississippian (cherty)
3196 - 3250	Lime
3250 - 3335	Lime and shale
3335 - 3396	Shale and lime
3396 - 3398	Hunton
3398 -	Rotary Total Depth

State of Kansas)
Sedgwick County) SS

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON & SONS DRILLING CO.

By Harry D. Fickman

Subscribed and sworn to before me this 23rd day of May, 1958.

Lorraine Shilloutt
Notary Public

My commission expires June 1, 1960.