


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

MCPHERSON County. Sec. 12 Twp. 21S Rge. 1W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner UNION TEXAS PETROLEUM  
Lease Name GOOSSEN Well No. 4  
Office Address 1740 BROADWAY, DENVER, COLORADO  
Character of Well (completed as Oil, Gas or Dry Hole) INPUT  
Date well completed SEPTEMBER 6 19 58  
Application for plugging filed MAY 12 19 66  
Application for plugging approved MAY 16 19 66  
Plugging commenced JULY 13 19 66  
Plugging completed JULY 30 19 66  
Reason for abandonment of well or producing formation POOL BEING ABANDONED

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR HUGH SCOTT  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3530 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221'	NONE
				5 1/2"	3449'	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3530 - 3050 - PLUG  
3050 - 3045 - SAND  
3045 - 3005 - 5 SACKS CEMENT  
3005 - 200 - MUD  
200 - 190 - ROCK BRIDGE  
190 - 115 - 25 SACKS CEMENT  
115 - 40 - MUD  
40 - 30 - ROCK BRIDGE  
30 - BASE - 10 SCKS CEMENT

RELEASED BY  
STATE CORPORATION COMMISSION

AUG 2 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC  
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T.L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.L. Nutt

BOX 562, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of JULY, 19 66

My commission expires JULY 31, 1966

Mary M. Sweeney  
Notary Public.

DRILLERS' LOG

Well Owner: Anderson-Prichard Oil Corporation  
 Farm Name: Goossen Well No. 4  
 Commenced: 8/20/58  
 Completed: 9/1/58  
 Total Depth: 3530'  
 Casing: 8 5/8" @ 221' cemented  
 5 1/2" @ 3449' cemented  
 Contractor: Peel Brothers, Inc.

NE NE NE  
 Sec. 12-21S-1W  
 McPherson County, Kansas  
 Elevation:  
 Production:

Figures below indicate bottoms of formations:

Sand and clay	0 -	80
Shale		221
Shale and lime		810
Lime		960
Lime and shale		1435
Shale and shells		1665
Shale and lime		2170
Shale		2240
Sand		2275
Shale		2335
Shale and lime		2530
Lime		2615
Lime and shale		2675
Lime		2760
Lime and shale		2935
Lime		2990
Lime and chert		3017
Chert		3060
Lime and chert		3150
Lime		3240
Shale and lime		3520
Sand		3530
Total Depth		3530

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 2 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY Jack Matta

SUBSCRIBED AND SWORN to before me this 2nd day of September, 1958

My commission expires: April 27, 1960

Luck Brack  
 Notary Public