

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY KEARNEY SEC. 21 TWP. 21S RGE. 35 NW
Location as in quarters or footage from lines:
C-NW-SE

Locate Well
correctly on above
Section Platt.

Lease Owner THUNDERBIRD DRILLING INC.
Lease Name WINGATE Well No. 1
Office Address Box 97 ELLINWOOD, KS 67526
Character of Well (Completed as Oil, Gas or Dry Hole): OIL
Date Well Completed 5/9/85
Application for plugging filed 5/29/85
Plugging commenced JUNE 7 1985
Plugging completed JULY 30 1985
Reason for abandonment of well or producing formation NOT COMMERCIAL

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well STEVE DURANT
Producing formation MARMATON Depth to top 4458 bottom 4464 T.D. PB 4533
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		<u>SURF.</u>	<u>388</u>	<u>8 5/8"</u>	<u>388</u>	<u>ZERO</u>
		<u>SURF.</u>	<u>4585</u>	<u>4 1/2"</u>	<u>4585</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. NO PIPE RECOVERY. STAGE COLLAR AT 2488. CEMENTED TO SURFACE WITH 535 SAX. 6/7/85. ALLIED CEMENTING PUMPED 3 SAX HULLS, 40 SAX CEMENT, 25 SAX GEL & HAD 7 SAX CEMENT MIXED & WELL QUIT TAKING. RENT TO 3700' ON 4 1/2 CIG. SHUT DOWN. 7/26/85 MOVED IN CABLE TOOL RIG. 7/29/85. DRILLED & CLEANED OUT TO 1100'. SWABBED & BAILED DOWN TO 1100'. 7/30/85 ALLIED MIXED & PUMPED APPX 90 SAX. FILLED 4 1/2" TO SURFACE. CEMENT WAS 50-50 P&S MIX 6% GEL 390 CCL PLUGGING COMPLETED 10:15 AM 7/30/85

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor THUNDERBIRD DRILLING & ALLIED CEMENTING

STATE OF KANSAS COUNTY OF BARTON, ss.
MAYNARD WEBER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maynard Weber
Box 97 ELLINWOOD, KS 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1985

Trevlyn Detmer
Notary Public.

My Commission expires Jan. 21, 1986
TREVLYN DETMER
Barton County, Kansas
My Appt. Exp. Jan. 21, 1986

RECEIVED
STATE CORPORATION COMMISSION

JUN 31 1985