

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-055-20,950.0000

LEASE NAME Foster

WELL NUMBER 2-18

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3300' Ft. from S Section Line

4100' Ft. from E Section Line

LEASE OPERATOR Lebsack Oil Production, Inc.

SEC.18 TWP.21S RGE.34 (E) or (W)

ADDRESS P.O. Box 489, Hays, KS 67601

COUNTY Finney

PHONE#( 913 ) 625-3046 OPERATORS LICENSE NO. 5210

Date Well Completed \_\_\_\_\_

Character of Well D&A

STATE CORPORATION COMMISSION

Plugging Commenced 1-4-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well) JAN 15 1991 Plugging Completed 1-4-91

The plugging proposal was approved on 1-4-91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each, set.  
Fill w/heavy mud; set 1st plug @ 2700'-2300' w/100 sx; 2nd plug @ 1270'-950' w/80 sx; 3rd plug @ 630'-430' w/50 sx; 4th plug @ 300'-100' w/50 sx; 5th plug @ 40'-surface w/10 sx; Rathole 15 sx; mousehole 10 sx; 60-40 pozmix 6% gel 1/4# Flocel per sack.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202 STATE OF \_\_\_\_\_ COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of January, 19 91



Angela Woodard  
Notary Public

My Commission Expires: 3-20-93