

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,050-0000

LEASE NAME Christabelle

WELL NUMBER 1

SPOT LOCATION C SW NW

SEC. 18 TWP. 21 SRGE. 34 (E) of (X)

COUNTY Finney

Date Well Completed 11-4-71

Plugging Commenced 7-6-84

Plugging Completed 7-9-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oakwood Resources Inc.

ADDRESS P. O. Box 740516 Dallas, Texas 75374-0516

PHONE # (214) 680-8686 OPERATORS LICENSE NO. 8563

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City (Mr. Paul Luthi)

Is ACO-1 filed? No If not, is well log attached? No, (Form C-10-1972 was filed)

Producing formation Krider Depth to top 2,652' bottom 2,664' T.D. 5,065'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	302'	None
<u>Krider</u>	<u>Gas</u>	<u>2,652'</u>	<u>2,664'</u>	<u>4 1/2"</u>	<u>4,995'</u>	<u>757'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pump 25 sks. of cement @ 2,664' to 2,300'

Pump 40 sks. of cement @ 725' to 625'

Pump 50 sks. of cement @ 350' to 250'

Put 10 sks. of cement @ 40' to 0'

Cut off & cap 8 5/8" csg. 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547
Address P.O. Box 506 Liberal, Kansas 67901

STATE OF Texas COUNTY OF Dallas, ss.

J. Michael Warren (employee of operator) or
~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Michael Warren

(Address) P.O. Box 740516 Dallas, Tx. 75374-0516

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 84

Beverly [Signature]
Notary Public

My Commission expires: 12-31-84

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1984

CONSERVATION DIVISION
Wichita, Kansas