

To: 1 052192
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 185-21,666.0000
SE NW SE, SEC. 27, T 21 S, R 12 WEX
1650 feet from S section line
1650 feet from E section line
Lease Name Shumway Well # 4
County Stafford 118.14
Well Total Depth 3635 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 300

Operator License / 6039
Operator: L.D. Drilling, Inc.
Name &
Address Rt. 1, Box 183 B
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 10 Month: 11 Year: 1997

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

core: 5 1/2" at 3627' w/150 sx cement, Perfs at 3335-3488'

1st plug sand back to 3280' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 10 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3280' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi. 11-18-1997

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2820' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did ~~not~~) observe this plugging.

DATE NOV 21 1997

INV. NO. 49550

Signed Richard W. Lacey
(TECHNICIAN)