

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21158-00-01
Spot: CNESWSE Sec/Twnshp/Rge: 27-21S-12W
990 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SHUMWAY Well Number: 3
County: STAFFORD Total Vertical Depth: 3650 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 8 118.63
Surface Casing: Size 8.625 feet: 333 WITH 255 SX CMT
Production: Size 4.5 feet: 3633 WITH 175 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E27382.1 Date/Time to Plug: 03/28/2002 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3290' WITH 4 SX CMT. 1ST PLUG AT 650' WITH 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE
Date/Time Plugging Completed: 03/28/2002 12:05 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3595'. PERFS AT 3341-3441'. SANDED TO 3290' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
APR 02 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2340' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4-3-02
INV. NO. 2002061605
MAR 29 2002
MD