

1 052096

API NUMBER 15- 185-20,797-0001

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

SE NE NE, SEC. 27, T 21 S, R 12 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License / 6039  
Operator: L.D. Drilling, Inc.  
Name  
Address RR 1, Box 183 B  
Great Bend, KS 67530

4290 feet from S section line  
330 feet from E section line

Lease Name Siefkes OWWO Well # 3  
County Stafford

Well Total Depth 3695 120.08 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing License Number 6901

Address Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 16 Month: 12 Year: 1996

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing (phone) 316-587-3361

logs: 5 1/2" at 3694' w/140 sx cement. Perfs at 3252-3654'

1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 p.m. Day: 16 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3200' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1709' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED  
DATE JAN 03 1997

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 47227