

15-185-01901-00-01

1052232

TO: 3-16 API NUMBER Drilled November 1943

STATE CORPORATION COMMISSION NW NW SW, SEC. 18, T 21 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 2330 FEET FROM SOUTH SECTION LINE 120.90

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME Welsh A WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY Stafford 120.90 11/10/98 Whitor

OPERATOR LICENSE # 31798 WELL TOTAL DEPTH 3720 FEET

OPERATOR: Xanadu Exploration Company PRODUCTION CSG: SIZE 5 1/2" FEET 3554

NAME AND 6 East 5th Street, Suite 200 SURFACE CASING: SIZE 10 3/4" FEET 285

ADDRESS Tulsa, OK 74103

ABANDONED OIL WELL      GAS WELL      INPUT WELL      SWD WELL E-6117 D/A     

OTHER WELL AS HEREINAFTER INDICATED     

PLUGGING CONTRACTOR L. D. Drilling inc. LICENSE NUMBER 6039

ADDRESS RR 1, Box 183-B Great Bend, KS 67530

COMPANY TO PLUG AT: HOUR: 10:00 am DAY: 16 MONTH: 3 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Mike Kasselmann

(COMPANY NAME) L. D. Drilling Inc. (PHONE) 316-793-3051

WERE: TO pump down the 5 1/2" casing with 300# hulls- 25sx cement-21 sx of gel-115 sx

of cement. Pump down 10 3/4" X 5 1/2" annulas with 50 sx of cement. Use 60/40 pozmix

6% gel for the cement blend.

PLUGGING PROPOSAL RECEIVED BY Steve Durrant

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART      NONE     

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 16 MONTH: 3 YEAR: 1998

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing with: 300# of cottensed hulls -

25 sx of cement - 21 sx of gel - 115 sx of cement. Maximum pressure =500 psig

Shut in pressure = 50 psig

Pumped down 10 3/4" X 5 1/2" annulas with 50 sx of cement

Maximum pressure = 200 psig. Shut in 50 psig 08 21 12 11 11 11

5 1/2" casing had been squeezed 1614' 1115' 595' in October 1982

REMARKS: USED 60/40 pozmix 6% gel cement pumped by Allied Cementing. RECEIVED  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacy  
(TECHNICIAN) FORM CP-2/3

INVOICED  
DATE 3-25-98  
INV. NO. 50314