

1052392

15-185-12902-0000

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED IN 1953 NE SW SW SEC. 18, T 21 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WELSH "A" WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 117.88

OPERATOR LICENSE # 31798

WELL TCTAL DEPTH 3627 FEET

OPERATOR: XANADU EXPLORATION CO. PRODUCTION CSG: SIZE 5 1/2" @ 3625' WITH SX

NAME AND 6 E 5TH, #200 SURFACE CASING: SIZE 8 3/4" @ 293' WITH SX

ADDRESS TULSA, OK 74103

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR KLIMA WELL SERVICE, INC. LICENSE NUMBER 7023

ADDRESS 610 WEST FRONT STREET CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 18 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM LARRY SWEET WITH XANADU

(COMPANY NAME) KLIMA WELL SERVICE, INC (PHONE) 316-587-3333

WERE: PERFS AT 3302-3304, 3308-3315, 3391-95, 3402-3409, 3542-3547, 3554-3560, 3571-3580 3551-63. TOP OF CEMENT AT 2982'.

PACKER AT 3500'. TOP OF TUBING FISH 2730'. 1ST PLUG AT 1456' WITH 15 SX GEL AND 50 SX CEMENT. 2ND PLUG AT 1196' WITH 50 SX CEMENT. 3RD PLUG AT 711' WITH 50 SX CEMENT. 4TH PLUG AT 323' WITH 50 SX CEMENT. 5TH PLUG AT 65' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:31 PM DAY: 18 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

PACKER AT 3500'. TOP OF TUBING FISH 2730'. 1ST PLUG AT 1456' WITH 15 SX GEL AND 50 SX CEMENT. 2ND PLUG AT 1196' WITH 50 SX CEMENT. 3RD PLUG AT 711' WITH 50 SX CEMENT. 4TH PLUG AT 323' WITH 50 SX CEMENT. 5TH PLUG AT 65' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 2% GEL 3% BY ALLIED. RECOVERED 1597' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICE SIGNED DATE 5/25/00 61782

Richard M. Lacey (TECHNICIAN) FORM CP-2/3

RECEIVED MAY 24 2000 CONSERVATION DIVISION Wichita, Kansas

Handwritten signature and circled 'R'