

To: 1 052155 7-28
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-Drilled 8/8/50 15.185.12664.0000

NW SE SE, SEC. 18, T 21 S, R 12 W/X

990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6461

Lease Name Cora Clark Well # 3

Operator: Landers & Musgrove

County Stafford 116.25

Name & Address P.O. Box 266

Well Total Depth 3577 feet

Okemah, OK. 74859

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 28 - Month: 7 Year: 19 97

Plugging proposal received from Rob Long

(company name) Landers & Musgrove (phone) 918-623-2740

Core: 5 1/2" at 3567'

Fill casing with cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 28 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT Drilled tubing to 1997'. Tubing plugged, pulled tubing. Ran back in to 1025', could not get any further.

1st plug pumped 25 sx cement at 1025';

2nd plug pulled tubing to 700' and pumped 10 sx gel and 50 sx cement,

3rd plug pulled tubing to 260' and pumped 50 sx cement,

4th plug pulled tubing to 40' and pumped 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 880' of 5 1/2" casing. 8-12-1999
(If additional description is necessary, use BACK of this form.)

I (date) 8-13-97 observed this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 8-13-97

INV. NO. 48786