

1052226

15-185-13075-00-D1

TO: 2-16 API NUMBER 15- Docket #E-25,028

STATE CORPORATION COMMISSION S/2 SE SE, SEC. 19, T 21S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME William A. McCrary WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY Stafford 116.29

OPERATOR LICENSE # 6039 WELL TOTAL DEPTH 3578 FEET

OPERATOR: L.D. Drilling, Inc. PRODUCTION CSG: SIZE 7" FEET 3575 w/150 sx

NAME AND RR 1, Box 183 B SURFACE CASING: SIZE 10 3/4" FEET 280

ADDRESS Great Bend, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL X SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D S & W Well Servicing, Inc. LICENSE NUMBER 6901

ADDRESS P.O. Box 231, Claflin, KS 67525-0231

COMPANY TO PLUG AT: HOUR: 11:30 a.m. DAY: 16 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Kent Strube

(COMPANY NAME) D S & W Well Servicing, Inc. (PHONE) 316-587-3361

WERE: Perfs at 3336-3474'

1st plug sand back to 3280' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel, 75 sx cement and 5 sx gel at 660',

3rd plug pump 75 sx cement at 310', 4th plug pump 15 sx cement at 40'.

PLUGGING PROPOSAL RECEIVED BY Richard Lacey

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 1:30 p.m. DAY: 16 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT TO 1st plug sanded back to 3280' and dumped 7 sx cement on top of

sand through bailer,

Pumped through casing: 2nd plug at 660' with 10 sx gel, 75 sx cement, and 5 sx gel,

3rd plug at 310' with 75 sx cement,

4th plug at 40' with 15 sx cement.

FEB 23 1998

REMARKS: Used 60/40 Pozmix 6% gel by Allied. Recovered 680' of casing. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM?)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

DATE FEB 25 1998

NV. NO. 50134