

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-13068-00-00  
Spot: CNWNWNW Sec/Twnshp/Rge: 19-21S-12W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease/Unit Name: E.B.HALL Well Number: 1  
County: STAFFORD Total Vertical Depth: 3597 feet

Operator License No.: 4967  
Op Name: BERENERGY CORPORATION  
Address: PO BOX 5850  
DENVER, CO 80217

Conductor Pipe: Size feet:                       
Surface Casing: Size 8.625 feet: 266 WITH 300 SX CMT \$116.90  
Production: Size 5.5 feet: 3583 WITH 150 SX CMT  
Liner: Size feet:                     

Well Type: OIL UIC Docket No:                      Date/Time to Plug: 11/06/2001 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from:                      Company:                      Phone:                     

Proposed Plugging Method: CIBP @ 3206' WITH 2 SX CMT. PERFORATE AT 700'. RUN TUBING TO 700'. PUMP 350 SX CMT UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. CIRCULATE CMT. PULL TUBING AND TOP OFF HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/07/2001 9:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3551'. PERFS AT 3304-3494'. SET CIBP @ 3206' PLACED 2 SX CMT ON TOP OF CIBP WITH BAILER. PERFORATED 5 1/2" AT 700'. RAN TUBING TO 700'. PUMPED 460 SX CMT THROUGH TUBING UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. CIRCULATED CMT. PULLED TUBING AND TOPPED OFF HOLE WITH 65 SX CMT. COULDN'T LOAD. 11/07/01: TOC @ 113'. PUMPED 10 SX CMT DOWN 5 1/2". PUMPED 10 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. CSG HAS HIGH LEAKS.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

NOV 21 2001

INVOICE NOV 13 2001

KCC WICHITA

DATE 11-26-01

TRF. NO. 2002060973

[Signature]  
Form CK-2/3