

1 010171

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8709

Operator: White Oilfield Supply, Inc.  
Name: \_\_\_\_\_  
Address: 906 South Iowa  
Pratt, Ks 67124

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P.O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 2:15 p.m. Day: 2-5 Month: 9 Year: 19 86

Plugging proposal received from Wayne Bougner

(company name) Aldebaran Drilling Co. (phone) 316-672-7471

were: To fill hole with heavy mud and spot cement Elevation 2079' GL  
through drill pipe

1st plug at base anhydrite with 50 sx cement

2nd plug at 30' below surface pipe with 50 sx cement

3rd plug at 40' with 10 sx cement

4th plug to circulate rathole with 10 sx cement, 5th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 2-5 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement

2nd plug at 430' with 40 sx cement

3rd plug at 40-0' with 10 sx cement

4th plug to circulate rathole with 10 sx cement

5th plug to circulate mousehole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

INVOICED (old) observe this plugging.

DATE 9-29-86

INV. NO. 15022

API NUMBER 15- 151-21,809 - 0000

SW SE NW SEC. 21, T 28 S, R 15 W/E

2970 feet from S section line

3630 feet from E section line

Lease Name Baker Well # 2

County Pratt 158.96

Well Total Depth 4891 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 400

*Rec'd 9-29-86*

SEP 29 1986

Signed *Jack Luthi*  
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date SEPTEMBER 18 1986 month day year

API Number 15- 151-21,809 East SW SE NW Sec. 21 Twp. 28 S, Rg. 15 X West 2970' 3630' Ft. from South Line of Section Ft. from East Line of Section

OPERATOR: License # 8709 Name WHITE OILFIELD SUPPLY, INC. Address 906 SOUTH IOWA City/State/Zip PRATT, KANSAS 67124 Contact Person RUSS WHITE Phone (316) 672-7130

Nearest lease or unit boundary line 330' feet County PRATT Lease Name BAKER #2 Well # #2 Ground surface elevation 2079 feet MSL

CONTRACTOR: License # 5529 Name ALDEBARAN DRILLING CO., INC. City/State WICHITA, KANSAS

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 200 Depth to bottom of usable water 250 Surface pipe planned to be set 400' Projected Total Depth 4900' feet Formation SIMPSON

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary X Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 9-16-86 Signature of Operator or Agent MICHAEL W. KIRKMAN Title VICE-PRESIDENT

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 260 feet per ft. This Authorization Expires 3-16-87 Approved By 9-16-86

Move in 9-18-86 at 8 5/8 400'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, feet depth with, sxs of, and material. Includes entries for 1st plug @ 880', 2nd plug @ 360', 3rd plug @ 40', 4th plug @, 5th plug @, and (2) Rathole with 10 sxs.

PUSHER Wayne Bonner ID 4891 FORMATION MISS SURFACE PIPE 8 5/8 @ 400 ANHYDRITE ELEVATION 2079 STARTING TIME & DATE 2:15 pm 9-26-86 COMPLETION TIME & DATE 4:00 pm 1st PLUG @ 1000 FT. W/ 50 SX 2nd PLUG @ 430 FT. W/ 40 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton 6/4 6 1/4 9/29 TECHNICIAN JACK LUTHE Witnessed all -