

To: 070005

6-23

API NUMBER 15- 097-21,019-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION App. E/2 NW NE, SEC. 17, T 28 S, R 16 W/EX
130 S. Market, Room 2078
Wichita, KS 67202

540 feet from N section line

1620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31629

Lease Name Chenoweth Well # 1

Operator: Nash Oil & Gas, Inc.

County Kiowa 157.76

Name & Address 30060 N. 281 Hwy.

Well Total Depth 4854 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 456

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 12:30 p.m. Day: 23 Month: 6 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 4836' w/250 sx cement, PBD 4836', Perfs at 4743-53'

1st plug sand back to 4690' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:55 p.m. Day: 23 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2380' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 03 1997

INV. NO. 48485

Signed [Signature] (TECHNICIAN)