

To: 1 031010
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-25

API NUMBER 15-097-21,070-0000
NE NE NW, SEC. 17, T 28 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9158
Operator: Case Oil & Gas
Name & Address 1251 South Clay, Suite 3
Liberal, KS 67901

4950 feet from S section line
2970 feet from E section line
Lease Name Greiner Well # 1
County Kiowa 157.79
Well Total Depth 4855 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 25 Month: 5 Year: 19 89

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4853' Perfs at 4714-20, 4740-45, 4756-60' Elevation 2147' GL
1st plug sand back to 4660' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 25 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 5 sx cement on top of
sand through bailer.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

Mike Spain also witnessed this plugging.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2605' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE 6-2-89

Signed Steve Runout
(TECHNICIAN)

INV. NO. 24948
5-25