

To: 1.070006
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App.
130 S. Market, Room 2078
Wichita, KS 67202

6-23

API NUMBER 15- 097-21,122 - 0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 31629
Operator: Nash Oil & Gas, Inc.
Name & Address 30060 N. 281 Hwy.
Pratt, KS 67124

NE NE NE, SEC. 17, T 28 S, R 16 W/X
4930 feet from S section line
350 feet from E section line
Lease Name Chenoweth Well # 2
County Kiowa 159.25
Well Total Depth 4900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 2:55 p.m. Day: 23 Month: 6 Year: 1997

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at ?, Perfs est. 4750'

1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:50 p.m. Day: 23 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer, 6-26-97

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2353' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~XXXXXX~~) observe this plugging.

DATE Jul 03 1997
INV. NO. 48484

Signed [Signature] (TECHNICIAN)

MASSACHUSETTS CORPORATION
JUL 26 1997