

12-5 15.185.01854.0000

1 120172

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 12/16/55

NW NE SE, SEC. 4, T 21 S, R 14 W/E

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Asher Well # 2

Operator: Woodman-Iannitti Oil Company

County Stafford 116.97

Name & Address Box 308

Well Total Depth 3599 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 830

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 5 Month: 12 Year: 19 88

Plugging proposal received from Dick Iannitti

(company name) Woodman-Iannitti Oil Company (phone) 316-792-1934

were: 5 1/2" at 3598.5' w/100 sx cement PBD 3400' Perfs at 3297-3306'

1st plug sand back to 3245' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1988
12-9-1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 5 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3245' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 5 sx gel, 50 lbs. hulls and 100 sx cement.

Well was flowing SW approximately 1 gallon per minute.

Pumping pressure 500 psi to 850 psi and shut.in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2864' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I hereby observe this plugging.

Signed Dean Rankin
(TECHNICIAN)

DATE 12-12-88

INV. NO. 23380