

1 120434

6-12 15.185.01853.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 12/30/55

TECHNICIAN'S PLUGGING REPORT

Operator License # 3493

Operator: Reginald D. Fisher
Name & Address: 110 N. Exchange St.
St. John, KS 67576

NE NE NE, SEC. 4, T 21 S, R 14 W/E

4950 feet from S section line

330 feet from E section line

Lease Name Langer Well # 4

County Stafford 115.57

Well Total Depth 3556 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 811

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 11 Month: 6 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3555' Open hole

1st plug sand back to 3480' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 12 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3480' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

7 sx gel, circulated on backside of 8 5/8", ran tubing to 870' and pumped in 10 sx gel,

laid down one joint and pumped 50 sx cement at 840', circulated cement at 340'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1300' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-2-90 JUN 20 1990

Signed [Signature] (TECHNICIAN)

INV. NO. 28508 CONSERVATION, Wichita, Kansas