

1 080536

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,376.0000

NW NE NE, SEC. 4, T 21 S, R 14 W

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5122

Lease Name Langer Well # 2

Operator: Woodman-Iannitti Drilling Co.
Name & Address P. O. Box 308
Great Bend, KS 67530

County Stafford 115.93

Well Total Depth 3567 Arbuckle 7' feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 809

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address P. O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 3 Month: July Year: 19 86

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1920
Anhydrite N/A

1st plug 30' below the base of the surface pipe with 50 sx cement

2nd plug at 300' with 25 sx cement

3rd plug from 40' to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement

5th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:00 am Day: 3 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, 2nd plug at 300' with 25 sx

cement, 3rd plug from 40' to surface with 15 sx cement, 4th plug to circulate rat hole

with 15 sx cement, 5th plug to circulate mouse hole with 10 sx cement. Circulated

cement in the water well.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 14 1986

INV. NO. 14374

observe this plugging
STATE CORPORATION COMMISSION

JUL 11 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] (TECHNICIAN)