

To: 1 120594
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-19 209
API NUMBER 15- 185-21,020.0000
NE NE NW, SEC. 4, T. 21 S, R. 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783
Operator: Galloway Drilling Company, Inc.
Name & Address 105 S. Broadway, Suite 340
Wichita, KS 67202

4950 feet from S section line
2970 feet from E section line
Lease Name Boyd Well # 2
County Stafford 116.09
Well Total Depth 3572 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 826

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 7 Year: 19 91

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3570' w/125 sx cement, Perfs at 3449-3451', 3533-35'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 19 Month: 7 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3400' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 11 sx gel, 100 lbs. hulls,
50 sx cement, 9 sx gel, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2540' of 5 1/2" casing. Co. _____
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 8-8-91
INV. NO. 32594

Signed [Signature]
(TECHNICIAN)