

To: 1 041153
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 12/81 15-195-10113.0001
S/2 S/2 SE, SEC. 10, T 21 S, R 14 W/E
330 feet from S section line
1320 feet from E section line

3-1
TECHNICIAN'S PLUGGING REPORT

Operator License # 30081

Lease Name Anshutz Well # 2 OWWO

Operator: Anshutz Oil

County Stafford

Name & Address Rt. 1, Box 46

Well Total Depth 3645 118.46 feet

Seward, KS 67577

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor O.G.H. Oil Co. License Number 3154

Address Rt. 1, Box 87, Wilson, KS 67490

Company to plug at: Hour: 10:30 a.m. Day: 1 Month: 3 Year: 19 96

Plugging proposal received from Larry Dolechek

(company name) O.G.H. Oil Co. (phone) 913-658-3528

logs: 4 1/2" at 3645' w/175 sx cement, Perfs at 3590-93, 3529-32, 3490-95'

1st plug sand back to 3440' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 1 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3440' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10

sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Maximum pressure 650 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1120' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE MAR 13 1996

INV. NO. 45035

Signed *Steve Pfeifer*
(TECHNICIAN)

RECEIVED
KANSAS CORP COMM
99B MAR -7 A 11:23