

To: 1041154  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-20,427.0000  
S/2 SW SE, SEC. 10, T 21 S, R 14 W/EX

3-1  
TECHNICIAN'S PLUGGING REPORT  
Operator License # 30081  
Operator: Anshutz Oil  
Name & Address: Rt. 1, Box 46  
Seward, KS 67577

330 feet from S section line  
1980 feet from E section line  
Lease Name Anshutz Well # 1  
County Stafford  
Well Total Depth 3709 120.54 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor O.G.H. Oil Co. License Number 3154

Address Rt. 1, Box 87, Wilson, KS 67490

Company to plug at: Hour: 12:45 p.m. Day: 1 Month: 3 Year: 1996

Plugging proposal received from Larry Dolechek

(company name) O.G.H. Oil Co. (phone) 913-658-3528

were: 5 1/2" at 3706' w/150 sx cement, Perfs at 3680-84, 3486-92'

1st plug sand back to 3435' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 p.m. Day: 1 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3435' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1780' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If possible, request observer to observe this plugging.)

DATE MAR 13 1996

INV. NO. 45034

Signed Steve Pfeifer  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION  
MAR 7 AM 23